



## S37 Klagenfurter Schnellstraße - Kunstabautenplanung

Für die S 37 Klagenfurter Schnellstraße ist ein Ausbau zur Erhöhung der Verkehrssicherheit im Abschnitt zwischen St. Veit Nord und Maria Saal geplant. Dieser soll in zwei Ausbaustufen (Abschnitt Nord und Abschnitt Süd) realisiert werden. Das Baulos 1 des Abschnitts Nord erstreckt sich von km 283,0 bis km 285. Der bestehende Querschnitt wird an der Westseite auf eine Gesamtbreite von 20,60 m verbreitert. Dazu sind alle Längsbrücken der S 37 zu verbreitern, die Unterführungen entsprechend zu verlängern und die Überführungen neu zu errichten.

**Auftraggeber :** Asfinag Baumanagement GmbH  
Modcenterstraße 16/3  
1030 Wien

**Kontakt:** Ing. Erich Presslauer  
Tel.: +43(0)50108 / 14 255

### Bauwerksdaten:

Zu bearbeitende Objekte	Länge	Breite	Maßnahme
Überführung St.Veit Nord	51,0m	7,0m	Verbreiterung
Wimitzbachbrücke Siebenaich	76,0m	10,6m	Verbreiterung
Wegüberführung Scheiffling	338 m	8,0m	Neubau
Wegunterführung Wurzerhof	4,6m	11,2m	Verlängerung
Wegüberführung Taggenbrunn	43,7m	8,0m	Neubau
Schätzkosten:	€ 3.100.000,-- exkl. USt.		
Leistungszeitraum:	2015 - 2017		
Fertigstellung:	zurückgestellt		

### Von S+W zu erbringende Leistungen:

Vorprojekt  
Generelles Projekt  
Ausschreibungsprojekt  
Detailprojekt

## S37 Klagenfurter Schnellstraße- Design of the engineering constr.

A development of the road section from St. Veit North to Maria Saal of the S 37 Klagenfurter Schnellstraße is planned to enhance the road safety. This is realized by two development stages (a North and a South part). The first section of the development stage north stretches from km 283,0 to km 285. The existing cross section is to be widened on the Westside to a total width of 20,60m. Therefore all lengthwise oriented bridge constructions of the S 37 have to be widened, the underpasses lengthened and the overpasses new constructed.

**client:** Asfinag Baumanagement GmbH  
Modcenterstraße 16/3  
1030 Wien

**contact:** Ing. Erich Presslauer  
Tel.: +43(0)50108 / 14 255

### General information

Objects to be developed	Length	Width	Measure
Overpass St.Veit Nord	51,0m	7,0m	Widening
Wimitzbachbridge Siebenaich	76,0m	10,6m	Widening
Overpass Scheiffling	338 m	8,0m	New constr.
Underpass Wurzerhof	4,6m	11,2m	Lengthening
Overpass Taggenbrunn	43,7m	8,0m	New constr.
Estimated costs:	€ 3.100.000,-- excl. VAT		
Service period:	2015 - 2017		
completion:	shelved		

### services rendered by S+W:

preliminary design  
general design  
tendering  
detailed design

